BRUHATH BENGALURU MAHANAGARA PALIKE
Yelahanka Division, Yelahanka Zone

Executive Engineeer
Yelahanka Division
B.B.M.P. Bengaluru - 64
No:EE/YNK-D/E-PMT/04/2014-15 Dated: 31-10-2014

MODIFIED APPROVED TENDER SCHEDULE –'B'

Item No: 75

Name of Work:-Construction of flagging course and covering slabs to existing drains and Asphalting to roads in Judicial Layout in ward no:04

Sl	Description	Unit	Approved Qty	Rate Quoted by the Contractor Approved Rates Sri.H SURESH	
				Rate	Rate in Words
1	KSRRB 300-1,Earth work excavation by manual means in ordinary soil invlving an average horizontal throw up to 2 meters and an average lift uo to 1.5m,excavated surface levelled and sides neatly dresssed, the disposed earth to be levelled neatly after breaking of clods complete as per specifications(Item no19.1,Page no138,PWD SR 2014-15)	Cum	224.78	74.80	Rupees seventy four and paise eighty only
			57.59	74.84	Rupees seventy four and paise eighty four only
2	Removing B.S slab of drain and stacking	Sqm	979.21	57.74	Rupees fifty seven and paise seventy four only
3	Refixing stone slabs of drains and pointing in CM(1:3)	Sqm	979.21	74.84	Rupees seventy four and paise eighty four only
4	Providing granite slabs of selected quality roughly dressed and fixed in cement mortar (1:6) including fixing curing etc., complete do 7.5 cms thick	Sqm	419.66	639.36	Rupees six hundred thirty nine and paise thirty six only
5	KSRRB 4.1:6Providing and laying in position plain cement concrete mix 1:2:4 with cement @240kgs,with 20mm and down size graded granite metal coarse aggregates @0.69 cum and fine aggregates @0.459cum, machine mixed, concrete laid in layers not exceeding 15cms thick well compacted,in foundation,plinth and cills,including cost of all materials, labour, HOM of machineries, curing complete as per specifications.Specification no4.1,4.2 (Page.12 & Item No. 4.6)	Cum	58.40	5274.36	Rupees five thousand two hundred seventy four and paise thirty six only
6	KSRB 5-14: Providing and constructing precast concrete solid blocks with compressive strength not less than 35Kg/sqm with cement mortar 1:4 masonry (quoin, Jamb, closer blocks) with solid concrete blocks of size 40x20x20cms conforming to I.S: 2185/1965 in superstructure including cost of materials, labour charges, scaffolding, curing complete as per specifications. (P25/5.27)	Sqm	169.56	983.66	Rupees five hundred eighty three and paise sixty six only

74.84

Sl	Description	Unit	Approved Qty	Rate Quoted by the Contractor Approved Rates Sri.H SURESH	
				Rate	Rate in Words
7	KSRR 5-15: Providing and constructing Non load bearing wall with cement concrete solid blocks with compressive strength not less than 35Kg/sqm with cement mortar 1:4 masonry (quoin, Jamb, closer blocks) with solid concrete blocks of size 40x10x20cms conforming to I.S: 2185/1965 in superstructure including cost of materials, labour charges, scaffolding, curing complete as per specifications. (P25/5.28)	Sqm	169.56	717.43	Rupees seven hundred seventeen and paise forty three only
8	Providing and fixing Precast RCC Slabs as Per approved design, specification and Direction Engineer-in-Charge. (Approved Data Rate).	Sqm	763.02	1232.55	Rupees one thousand two hundred thirty two and paise fifty five only
9	KSRRB M100-1 Loading and un loading of stone boulder/Stone aggregates/sand/kanker/Moorum.KSRRB M100-1:Placing tipper at loading point,loading with front end loader,dumping,turning for return trip,excluding time for haulage and return trip complete as per specifications(Item no17.1,Page no130,PWD SR 2014-15)	Cum	224.78	67.35	Rupees sixty seven and paise thirty five only
			57.59	67.36	Rupees sixty seven and paise thirty six only

Signature of the Contractor

Executive Engineer,
Yelahanka Division,
BBMP, Bengaluru-64.